

EXISTING COMPARTMENT WALL  
(INDICATIVE ONLY). 2 LAYERS OF  
PLASTERBOARD ON METAL STUDS.

PROCHECK FR200 VCL (BY OTHERS).

PRESSED 3mm GALV STEEL TOP HAT FIXED TO HORIZONTAL SFS  
AS PER BGP DESIGN AND CALCULATIONS FOR BACKUP WALL

GENIUS PRIME PANEL 3mm ALUMINIUM, FIXED TO 50mm  
HELPING HAND SYSTEM. PPC RAL 9006 METALLIC


SINIAT WEATHER DEFENCE BOARD FIXED TO VERTICAL TOPHAT  
AS PER MANUFACTURERS RECOMMENDATIONS. JOINTS SEALED  
USING SINIAT G-TEC WEATHER DEFENCE TAPE

50mm DUO SLAB FIXED AS PER MANUFACTURERS RECOMMENDATIONS

SIDERISE RV-90/60 WITH OSCI INSERT TO PANEL DEPTH, FIXED AS  
PER MANUFACTURERS RECOMMENDATIONS AS PER PROJECT SPEC  
CLAUSE 440X. INSTALL LOCATIONS AS SPECIFIED BY IFC  
(INTERNATIONAL FIRE CONSULTANTS) DATED 26TH MARCH 2021

PANEL SIZE INDICATIVE ONLY AND DEPENDANT ON LOCATION.

AS BUILT 19/11/21

C01	CONSTRUCTION ISSUE	RM	29/10/21
P01	FIRST ISSUE	RM	27/07/21
Rev	Description	By	Date
<div><div><b>AJ Cladding LTD</b> Architectural Cladding Specialists</div><div>19A Wilson Street, Hamilton, ML3 0NH  +44 (0) 1698 339 104 ajcladding.co.uk info@ajcladding.co.uk</div></div>			
Drawn By	RM	Date Created	27/07/21
Contract No.	2020	Scale	1:2.5
Contract Title	20: 20 HOUSE	ot	A3
Drawing Title	FIRE STRATEGY DETAIL AT RECESS CORNER		
Drawing No.	2020-PH01-FS-030	Rev	C01