

SINIAT WEATHER DEFENCE BOARD FIXED TO VERTICAL TOPHAT AS PER MANUFACTURERS RECOMMENDATIONS. JOINTS SEALED USING SINIAT G-TEC WEATHER DEFENCE TAPE.

50mm DUO SLAB FIXED AS PER MANUFACTURERS RECOMMENDATIONS.

GENIUS PRIME PANEL, 3MM ALUMINIUM, FIXED TO 50mm HELPING HAND SYSTEM. PPC TO RAL 9006 METALLIC.

SIDERISE RV-90/60 WITH OSCI INSERT TO PANEL DEPTH, FIXED AS PER MANUFACTURERS RECOMMENDATIONS AS PER PROJECT SPEC CLAUSE 440X. INSTALL LOCATIONS AS SPECIFIED BY IFC (INTERNATIONAL FIRE CONSULTANTS) DATED 26TH MARCH 2021.

FAST FRAME HELPING HAND SYSTEM FIXED TO GALV STEEL CHANNEL. CHANNEL FIXED AT TOPHAT LOCATIONS IN ACCORDANCE WITH FASTFRAME CALCS V7.

3mm ALUMINIUM CLOSURE FLASHING WITH PPC FINISH TO RAL 9006.

WINDOW DETAILS INDICATIVE ONLY (BY OTHERS).


PRESSED 3mm GALV STEEL TOP HATS AT 600mm CRS AS PER BGP CALCS FIXED TO HORIZONTAL SFS AS PER BGP DESIGN AND CALCULATIONS FOR BACKUP WALL. VERTICAL TOPHATS TO SIDES OF OPENINGS TO ACT AS FIRE BARRIER WITHIN VOID.

PRESSED 3mm GALV STEEL TOP HAT FIXED TO HORIZONTAL SFS AS PER BGP DESIGN AND CALCULATIONS FOR BACKUP WALL.

PROCHECK FR200 VCL (BY OTHERS).

EXISTING COMPARTMENT WALL (INDICATIVE ONLY). 2 LAYERS OF PLASTERBOARD ON METAL STUDS.

AS BUILT 19/11/21

C01	CONSTRUCTION ISSUE		RM	29/10/21	
P02	UPDATED AS PER WINTech COMMENTS 09/07/21		RM	29/07/21	
P01	FIRST ISSUE		RM	07/07/21	
Rev	Description		By	Date	
<div><div><div><div>AJ Cladding LTD</div><div>Architectural Cladding Specialists</div></div></div><div><div>19A Wilson Street, Hamilton, ML3 0NH</div><div>+44 (0) 1698 339 104 ajcladding.co.uk info@ajcladding.co.uk</div></div></div>					
Drawn By	RM	Date Created	07/07/21	Scale	1:2.5 of A3
Contract No.	2020				
Contract Title	20:20 HOUSE				
Drawing Title	FIRE STRATEGY DETAIL TO SOUTH FACE – INTERNAL CORNER.				
Drawing No.	2020-PH01-FS-027			Rev	C01